

4201 E 72ND AVE

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Government Building

YEAR BUILT

-

BUILDING AREA

10,856 SF

ROOF SQUARES

109

PARCEL ID

0172131300018



OVERALL ROOF CONDITION SCORE

66 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	single-ply membrane roof (exact chemistry not discernible from aerial imagery)
POSSIBLE TYPES	TPO/PVC (58%); Coating over membrane (45%); Modified bitumen (28%)
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; tree/debris exposure
ROOF AGE EST.	Appears moderate-age to aging based on widespread color variation and rooftop detailing; exact age unknown from imagery alone.
ROOF AREA	10,856 SF
ROOF PITCH	low-slope
CONFIDENCE	71%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		64/100
Ponding		72/100
Flashing & Seals		62/100
Penetrations		58/100
Overall Maintenance		61/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. The roof is predominantly a low-slope, light-colored membrane surface with parapet-like edges and multiple rooftop appurtenances.
3. Visible dark linear and patch-like features suggest seams, transitions, or maintenance-related components; exact system type cannot be confirmed from aerial imagery alone.
4. Localized discoloration is present in several areas, especially near roof sections and transitions, but no clear large-scale ponding is evident from this view.
5. Rooftop equipment, vents, and curbs are present and increase leak-prone detail density.

BUILDING CHARACTERISTICS

LAND AREA	2.08 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

This commercial low-slope roof appears serviceable but not pristine. The aerial view shows a generally intact light-colored membrane with multiple rooftop penetrations and several darkened/discolored areas that could reflect prior repairs, localized moisture retention, or surface wear. No obvious large ponding areas are visible, but the roof has enough detail and perimeter vegetation exposure to elevate maintenance and leak-risk concerns. The image date is 11/13/2025. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Continue routine roof inspections and maintenance, with emphasis on seams, flashing, curbs, penetrations, and areas of discoloration. Verify whether stained/darkened zones are cosmetic, repaired areas, or signs of recurring moisture. Trim nearby trees/vegetation where practical, and monitor drainage around roof transitions and equipment supports. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$293,383	Tear Off & Disposal	\$35,716
	Roof Membrane	\$71,432
	Insulation	\$43,370
	Flashing/Edging	\$28,063
	Labor	\$76,535
	Replacement Subtotal	\$255,116
	Contingency (15%)	\$38,267
	Total Project Cost	\$293,383

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$113,445	Overlay Subtotal	\$103,132
	Contingency (10%)	\$10,313
	Total Project Cost	\$113,445

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.