

5075 HIGHWAY 224

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Storage Warehouse

YEAR BUILT

-

BUILDING AREA

7,579 SF

ROOF SQUARES

76

PARCEL ID

0172131403004



OVERALL ROOF CONDITION SCORE

74 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	light-colored membrane roof (exact chemistry not verifiable from aerial imagery)
POSSIBLE TYPES	TPO/PVC (72%); coating over membrane (45%); metal (28%)
VISIBLE CONCERNS	many penetrations/units; tree/debris exposure; Several rooftop penetrations/vents/curbs are visible, including small rooftop units or vents concentrated near the roof edges and mid-roof.
ROOF AGE EST.	unknown; appears maintained and likely not near end-of-life based on visible surface uniformity
ROOF AREA	7,579 SF
ROOF PITCH	low-slope / near-flat
CONFIDENCE	76%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		68/100
Ponding		78/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		62/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. Large rectangular low-slope commercial roof with a bright, light-colored surface.
3. Surface appears relatively uniform with no clear widespread blistering, tears, or open seams visible from this height.
4. Multiple small penetrations and rooftop appurtenances are visible, which increases flashing and seal risk.
5. Vegetation is close to the roof edge on the right side, increasing debris accumulation and access/maintenance concerns.

BUILDING CHARACTERISTICS

LAND AREA	2.18 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

The roof appears to be a low-slope commercial membrane-style system with a light, uniform surface and generally serviceable appearance in the 11/13/2025 aerial image. Visible condition is reasonably good overall, but the roof has multiple penetrations/apurtenances and adjacent trees/vegetation that increase maintenance and leak-management risk. No clear widespread ponding or severe staining is apparent from the aerial view. Visible risk factors include high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Continue routine roof inspections and preventive maintenance, with attention to flashing around penetrations, edge details, and any areas near vegetation exposure. Trim back adjacent trees where feasible and monitor for debris accumulation. A closer field inspection is recommended to verify membrane type, evaluate sealant/flashing condition, and confirm there are no localized leaks or hidden deterioration not visible in aerial imagery.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$198,286	Tear Off & Disposal	\$24,139
	Roof Membrane	\$48,278
	Insulation	\$29,312
	Flashing/Edging	\$18,966
	Labor	\$51,727
\$22.75 / SF	Replacement Subtotal	\$172,422
	Contingency (15%)	\$25,863
	Total Project Cost	\$198,286

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$77,116	Overlay Subtotal	\$70,106
	Contingency (10%)	\$7,011
\$9.25 / SF	Total Project Cost	\$77,116

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.