

7200 QUEBEC PKWY

COMMERCE CITY CO 80022

PROPERTY TYPE

Commercial School - Elementary/Seco...

YEAR BUILT

-

BUILDING AREA

36,921 SF

ROOF SQUARES

369

PARCEL ID

0172133301001



OVERALL ROOF CONDITION SCORE

62 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof
ROOF SYSTEM	Single-ply membrane roof (likely white reflective membrane)
POSSIBLE TYPES	TPO/PVC (78%); Coating over membrane (56%); Modified bitumen (34%)
VISIBLE CONCERNS	dark staining/color variation; possible ponding; many penetrations/units
ROOF AGE EST.	Unknown from imagery; appears to be a maintained low-slope roof with multiple roof sections of mixed apparent exposure.
ROOF AREA	36,921 SF
ROOF PITCH	Low-slope / near-flat
CONFIDENCE	74%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		65/100
Ponding		55/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		68/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.
2. Large commercial school building with multiple interconnected low-slope roof sections.
3. White roof surfaces appear generally uniform and serviceable overall, with no widespread blistering or obvious catastrophic membrane failure visible from aerial view.
4. Localized darker patches and uneven coloration are present on some roof areas, especially near transitions and along portions of the roof perimeter.
5. Several rooftop mechanical units, vents, and penetrations are visible, increasing maintenance and flashing attention needs.

BUILDING CHARACTERISTICS

LAND AREA	8.60 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

The aerial image shows a large, low-slope commercial school roof that appears generally maintained and reflective, likely a white single-ply membrane or coated membrane system. Condition is tempered by localized dark staining/discoloration, possible minor ponding or retained moisture at select areas, and a complex roof layout with multiple penetrations and transitions. Overall risk is moderate rather than severe based on visible evidence. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.

Recommendation:

Continue routine roof inspections and maintenance, with emphasis on drainage, perimeter/transitional areas, and flashing around rooftop units and penetrations. Investigate the darker stained sections for signs of recurring moisture, ponding, or repaired areas. Because the report uses 11/13/2025 aerial imagery, a current field inspection is recommended to confirm whether the visible discoloration represents active water intrusion or benign staining.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,040,249	Tear Off & Disposal	\$126,639
	Roof Membrane	\$253,278
	Insulation	\$153,776
	Flashing/Edging	\$99,502
	Labor	\$271,369
\$24.50 / SF	Replacement Subtotal	\$904,564
	Contingency (15%)	\$135,685
	Total Project Cost	\$1,040,249

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$395,978	Overlay Subtotal	\$359,980
	Contingency (10%)	\$35,998
\$9.75 / SF	Total Project Cost	\$395,978

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.