

5101 QUEBEC ST

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Truck Stop Restaurant

YEAR BUILT

-

BUILDING AREA

5,853 SF

ROOF SQUARES

59

PARCEL ID

0182317107020



OVERALL ROOF CONDITION SCORE

62 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof with multiple connected sections
ROOF SYSTEM	Reflective membrane roof, likely TPO/PVC or coated membrane
POSSIBLE TYPES	TPO/PVC (68%); Coating over membrane (55%); Modified bitumen (28%)
VISIBLE CONCERNS	dark staining/color variation; possible ponding; many penetrations/units
ROOF AGE EST.	Unknown from aerial imagery; visible roof surface appears maintained but with signs of patching and localized wear
ROOF AREA	5,853 SF
ROOF PITCH	Low-slope / near-flat
CONFIDENCE	72%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		65/100
Ponding		55/100
Flashing & Seals		62/100
Penetrations		58/100
Overall Maintenance		64/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.
2. Multiple connected low-slope roof sections are visible over the commercial building.
3. The roof surface is predominantly bright white, suggesting a reflective membrane or coating.
4. Numerous rooftop penetrations and mechanical curbs are present, especially in the central and right portions of the roof.
5. Several localized dark patches and discoloration areas are visible, which may reflect repairs, staining, or moisture-related wear.

BUILDING CHARACTERISTICS

LAND AREA	4.17 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

The aerial imagery shows a large low-slope commercial roof with a bright reflective surface and many rooftop penetrations. Overall the roof appears serviceable, but localized dark staining/discoloration and the number of curbs, vents, and equipment units increase leak and maintenance risk. The image suggests a maintained roof with some patching or age-related wear rather than a uniform new installation. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.

Recommendation:

Perform a close-up roof inspection focused on seams, penetrations, curb flashings, and the darker stained areas to determine whether they reflect ponding, prior repairs, or active moisture intrusion. Verify drainage performance and check all rooftop units and flashings for seal integrity. Consider targeted maintenance or repairs where discoloration or repaired areas are concentrated. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$164,908	Tear Off & Disposal	\$20,076
	Roof Membrane	\$40,152
	Insulation	\$24,378
	Flashing/Edging	\$15,774
	Labor	\$43,020
\$24.50 / SF	Replacement Subtotal	\$143,398
	Contingency (15%)	\$21,510
	Total Project Cost	\$164,908

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$62,773	Overlay Subtotal	\$57,067
	Contingency (10%)	\$5,707
\$9.75 / SF	Total Project Cost	\$62,773

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.