

5200 E 56TH AVE

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Service Garage

YEAR BUILT

-

BUILDING AREA

11,021 SF

ROOF SQUARES

110

PARCEL ID

0182318106004



OVERALL ROOF CONDITION SCORE

74 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	coated or white reflective membrane roof
POSSIBLE TYPES	TPO/PVC (56%); coating over membrane (48%); modified bitumen (24%)
VISIBLE CONCERNS	many penetrations/units; Several rooftop units, vents, and curbs are present, increasing flashing and seal maintenance demand.; A few small dark rooftop features and localized rooftop equipment shadows are visible, but no clear widespread staining or ponding patterns are apparent.
ROOF AGE EST.	Exact age unknown from imagery; visible condition suggests a maintained roof with no obvious end-of-life distress, but age cannot be determined reliably from aerial view.
ROOF AREA	11,021 SF

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		82/100
Ponding		78/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		76/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include high penetration or rooftop-unit density.
2. Commercial service garage with extensive low-slope roof area and multiple adjoining roof sections.
3. Main roof surfaces appear bright, uniform, and generally clean in the aerial image.
4. Multiple rooftop mechanical units/vents are distributed around roof edges and at roof transitions, creating additional penetration and flashing locations.
5. No obvious membrane tears, severe blistering, or major ponding areas are visible from this overhead view.

BUILDING CHARACTERISTICS

LAND AREA	2.64 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

The roof appears to be a generally well-maintained low-slope commercial roof with a bright reflective surface and no clear signs of widespread ponding or heavy discoloration in the aerial image dated 11/13/2025. Serviceability risk is driven more by the number of rooftop units, vents, and roof transitions than by visible membrane distress. The imagery supports a likely reflective single-ply or coated roof assembly, but exact membrane chemistry cannot be confirmed from overhead imagery alone. Visible risk factors include high penetration or rooftop-unit density.

Recommendation:

Continue routine roof inspections and preventive maintenance, with particular attention to flashing, curbs, and sealant at mechanical penetrations. Monitor roof drains and low areas after storms for any developing ponding or discoloration. Reinspect in close-up if a field visit can confirm membrane type and verify seal conditions around rooftop equipment. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$288,337	Tear Off & Disposal	\$35,102
	Roof Membrane	\$70,204
	Insulation	\$42,624
	Flashing/Edging	\$27,580
	Labor	\$75,218
\$22.75 / SF	Replacement Subtotal	\$250,728
	Contingency (15%)	\$37,609
	Total Project Cost	\$288,337

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$112,139	Overlay Subtotal	\$101,944
	Contingency (10%)	\$10,194
\$9.25 / SF	Total Project Cost	\$112,139

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.