

5501 BRIGHTON BLVD

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Mega Warehouse

YEAR BUILT

-

BUILDING AREA

41,571 SF

ROOF SQUARES

416

PARCEL ID

0182512304004



OVERALL ROOF CONDITION SCORE

58 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	low-slope commercial warehouse roof
ROOF SYSTEM	likely single-ply membrane roof with multiple roof sections
POSSIBLE TYPES	TPO/PVC (48%); Coating over membrane (32%); Modified bitumen (24%)
VISIBLE CONCERNS	dark staining/color variation; possible ponding; many penetrations/units
ROOF AGE EST.	appears mid-life to older in service, with some sections showing wear and discoloration
ROOF AREA	41,571 SF
ROOF PITCH	low-slope / near-flat
CONFIDENCE	72%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 09/06/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		56/100
Ponding		54/100
Flashing & Seals		57/100
Penetrations		55/100
Overall Maintenance		56/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.
2. The property is a large commercial warehouse with multiple connected roof sections and a low-slope profile.
3. White roof segments are visible on the main buildings, with scattered dark stains and localized discoloration across several areas.
4. Tan/brown roof sections on the western/northern portions appear older or differently finished than the white sections.
5. Numerous small rooftop penetrations are visible, including vents/curbs, especially across the larger white roof areas.

BUILDING CHARACTERISTICS

LAND AREA	1.89 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

Aerial imagery dated 09/06/2025 shows a large low-slope commercial warehouse roof with multiple connected sections and a likely single-ply membrane roof system, though exact chemistry cannot be confirmed from overhead imagery alone. The roof appears generally serviceable, but visible dark staining, uneven coloration, and several roof penetrations suggest moderate maintenance and leak-management risk. Some sections appear newer or more reflective than others, indicating possible mixed-age roof areas or prior repair/recoat work. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density.

Recommendation:

Perform a close-up rooftop inspection to verify membrane type, check all flashing and penetration seals, and evaluate the stained/darker areas for active leaks, wet insulation, or drainage-related wear. Prioritize review of older-looking roof sections and any areas with concentrated discoloration or patch history. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,219,070	Tear Off & Disposal	\$148,408
	Roof Membrane	\$296,817
	Insulation	\$180,210
	Flashing/Edging	\$116,607
	Labor	\$318,018
	Replacement Subtotal	\$1,060,060
	Contingency (15%)	\$159,009
	Total Project Cost	\$1,219,070

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$457,281	Overlay Subtotal	\$415,710
	Contingency (10%)	\$41,571
	Total Project Cost	\$457,281

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.