

10900 E BRIARWOOD AVE

CENTENNIAL CO 80112

PROPERTY TYPE

Merchandising 2212

Com...

YEAR BUILT

-

BUILDING AREA

215,872 SF

ROOF SQUARES

2,159

PARCEL ID

207526210001

Image unavailable

OVERALL ROOF CONDITION SCORE

71 /100
FAIR

RISK LEVEL

MODERATE



Lower Risk Higher Risk

ROOF INFORMATION

ROOF TYPE	Low-slope membrane
ROOF SYSTEM	Unknown membrane
POSSIBLE TYPES	-
VISIBLE CONCERNS	None prominent from aerial image
ROOF AGE EST.	Unknown
ROOF AREA	215,872 SF
ROOF PITCH	Low slope
CONFIDENCE	Pending AI

SELECTED AERIAL IMAGE - ARAPAHOE COUNTY AERIALS AS OF 03/01/2024

ROOF CONDITION BREAKDOWN

Membrane Condition		71/100
Ponding		59/100
Flashing & Seals		63/100
Penetrations		69/100
Overall Maintenance		71/100

AERIAL ROOF OBSERVATIONS

- Aerial imagery is available, but AI analysis was not run for this report.
- Large low-slope roof area should be reviewed for membrane wear, drainage, staining, and penetration condition.
- Use the selected aerial image as the primary visual reference for field validation.

BUILDING CHARACTERISTICS

LAND AREA	24.46 acres
STORIES	-
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$11,358,528

REPORT SUMMARY

This preliminary report was generated from parcel/building data and aerial imagery. AI roof observations were not requested or no API key was available, so condition values are conservative placeholders for layout and workflow validation.

Recommendation:

Run AI image analysis and perform field inspection before final assessment.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$5,647,751	Tear Off & Disposal	\$687,552
\$22.75 / SF	Roof Membrane	\$1,375,105
	Insulation	\$834,885
	Flashing/Edging	\$540,220
	Labor	\$1,473,326
	Replacement Subtotal	\$4,911,088
	Contingency (15%)	\$736,663
	Total Project Cost	\$5,647,751

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$2,196,498	Overlay Subtotal	\$1,996,816
\$9.25 / SF	Contingency (10%)	\$199,682
	Total Project Cost	\$2,196,498

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.