

9800 E IKEA WAY

CENTENNIAL CO 80112

PROPERTY TYPE
Merchandising 2212

Com...

YEAR BUILT
-

BUILDING AREA
268,284 SF

ROOF SQUARES
2,683

PARCEL ID
207534436001



OVERALL ROOF CONDITION SCORE

69 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	white single-ply membrane roof with extensive rooftop solar arrays
POSSIBLE TYPES	TPO/PVC (76%); coated membrane (48%); ballasted membrane (22%)
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Localized dark streaking/discoloration is visible on the white field membrane, especially toward the right side and along some seams/penetration areas.
ROOF AGE EST.	apparent membrane age is indeterminate from aerial imagery; system appears serviceable but not new
ROOF AREA	268,284 SF
ROOF PITCH	very low / flat

SELECTED AERIAL IMAGE - ARAPAHOE COUNTY AERIALS AS OF 03/01/2024

ROOF CONDITION BREAKDOWN

Membrane Condition		66/100
Ponding		76/100
Flashing & Seals		62/100
Penetrations		56/100
Overall Maintenance		66/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.
2. Extensive solar PV coverage across most of the roof; the exposed membrane remains visible in multiple open areas.
3. White roof surface appears generally intact and uniformly reflective overall, but with scattered dark marks, streaking, and localized discoloration.
4. Multiple rooftop penetrations and mechanical/vent curbs are visible throughout the roof field.
5. No clear standing water or obvious severe membrane failure is visible from this aerial image.

BUILDING CHARACTERISTICS

LAND AREA	13.65 acres
STORIES	-
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$5,945,130

REPORT SUMMARY

The 03/01/2024 aerial image shows a large low-slope commercial roof with a white reflective membrane and extensive solar panel coverage. Visible evidence suggests generally serviceable roof condition, but localized discoloration/streaking and many penetrations reduce confidence in long-term watertightness from aerial review alone. The roof presents moderate maintenance and flashing risk typical of a heavily penetrated low-slope commercial roof. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.

Recommendation:

Continue routine roof inspections and preventative maintenance, with close attention to seams, flashings, curbs, and penetrations around the solar array and rooftop equipment. Investigate the darker stained areas during a field inspection to determine whether they reflect dirt, prior repairs, or moisture-related issues. Keep drains and rooftop details clear, and verify condition beneath and around solar attachments during the next service visit.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$7,250,375	Tear Off & Disposal	\$882,654
\$23.50 / SF	Roof Membrane	\$1,765,309
	Insulation	\$1,071,795
	Flashing/Edging	\$693,514
	Labor	\$1,891,402
	Replacement Subtotal	\$6,304,674
	Contingency (15%)	\$945,701
	Total Project Cost	\$7,250,375

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$2,803,568	Overlay Subtotal	\$2,548,698
\$9.50 / SF	Contingency (10%)	\$254,870
	Total Project Cost	\$2,803,568

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.