

1377 S JASON ST

DENVER CO 80223

PROPERTY TYPE

WAREHOUSE INDUSTRIAL-WAREHOUSE 39...

YEAR BUILT

1961

BUILDING AREA

70,847 SF

ROOF SQUARES

708

PARCEL ID

0521119012000

Image unavailable

OVERALL ROOF CONDITION SCORE

61 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Low-slope membrane
ROOF SYSTEM	Unknown membrane
POSSIBLE TYPES	-
VISIBLE CONCERNS	None prominent from aerial image
ROOF AGE EST.	65 years
ROOF AREA	70,847 SF
ROOF PITCH	Low slope
CONFIDENCE	Pending AI

SELECTED AERIAL IMAGE - AERIAL IMAGERY AS OF 03/11/2018 - 03/13/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		61/100
Ponding		49/100
Flashing & Seals		53/100
Penetrations		59/100
Overall Maintenance		61/100

AERIAL ROOF OBSERVATIONS

- Aerial imagery is available, but AI analysis was not run for this report.
- Large low-slope roof area should be reviewed for membrane wear, drainage, staining, and penetration condition.
- Use the selected aerial image as the primary visual reference for field validation.

BUILDING CHARACTERISTICS

LAND AREA	3.47 acres
STORIES	1
CONSTRUCTION TYPE	397: OFFICE/WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$3,609,800

REPORT SUMMARY

This preliminary report was generated from parcel/building data and aerial imagery. AI roof observations were not requested or no API key was available, so condition values are conservative placeholders for layout and workflow validation.

Recommendation:

Run AI image analysis and perform field inspection before final assessment.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,996,114	Tear Off & Disposal	\$243,005
	Roof Membrane	\$486,010
	Insulation	\$295,078
	Flashing/Edging	\$190,933
	Labor	\$520,725
\$24.50 / SF	Replacement Subtotal	\$1,735,752
	Contingency (15%)	\$260,363
	Total Project Cost	\$1,996,114

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$759,834	Overlay Subtotal	\$690,758
	Contingency (10%)	\$69,076
\$9.75 / SF	Total Project Cost	\$759,834

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.