

1314 W EVANS AVE

DENVER CO 80223

PROPERTY TYPE

MANUFACTURING INDUSTRIAL-FACTORY 4...

YEAR BUILT

1983

BUILDING AREA

96,700 SF

ROOF SQUARES

967

PARCEL ID

0528100060000

Image unavailable

OVERALL ROOF CONDITION SCORE

61 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Low-slope membrane
ROOF SYSTEM	Unknown membrane
POSSIBLE TYPES	-
VISIBLE CONCERNS	None prominent from aerial image
ROOF AGE EST.	43 years
ROOF AREA	96,700 SF
ROOF PITCH	Low slope
CONFIDENCE	Pending AI

SELECTED AERIAL IMAGE - AERIAL IMAGERY AS OF 03/11/2018 - 03/13/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		61/100
Ponding		49/100
Flashing & Seals		53/100
Penetrations		59/100
Overall Maintenance		61/100

AERIAL ROOF OBSERVATIONS

- Aerial imagery is available, but AI analysis was not run for this report.
- Large low-slope roof area should be reviewed for membrane wear, drainage, staining, and penetration condition.
- Use the selected aerial image as the primary visual reference for field validation.

BUILDING CHARACTERISTICS

LAND AREA	9.81 acres
STORIES	3
CONSTRUCTION TYPE	401: MFG/PROCESSING
TAX DISTRICT	DENV
LAND VALUE	\$6,952,000

REPORT SUMMARY

This preliminary report was generated from parcel/building data and aerial imagery. AI roof observations were not requested or no API key was available, so condition values are conservative placeholders for layout and workflow validation.

Recommendation:

Run AI image analysis and perform field inspection before final assessment.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$2,724,522	Tear Off & Disposal	\$331,681
	Roof Membrane	\$663,362
	Insulation	\$402,756
	Flashing/Edging	\$260,606
	Labor	\$710,745
\$24.50 / SF	Replacement Subtotal	\$2,369,150
	Contingency (15%)	\$355,372
	Total Project Cost	\$2,724,522

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,037,108	Overlay Subtotal	\$942,825
	Contingency (10%)	\$94,282
\$9.75 / SF	Total Project Cost	\$1,037,108

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.