

421 ZANG ST

LAKEWOOD CO 80228

PROPERTY TYPE
Public Office, Medical Building...

YEAR BUILT
1988

BUILDING AREA
36,947 SF

ROOF SQUARES
369

PARCEL ID
4908202002



OVERALL ROOF CONDITION SCORE

61 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof with multiple pitched/hipped roof sections
ROOF SYSTEM	unknown from aerial; likely a mix of low-slope membrane and sloped roofing
POSSIBLE TYPES	TPO/PVC (38%); Modified bitumen (24%); Coating over membrane (22%)
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; tree/debris exposure
ROOF AGE EST.	likely mid-life to aging for a 1988 building; exact roof age not determinable from aerial imagery
ROOF AREA	36,947 SF
ROOF PITCH	predominantly low-slope with multiple steep/sloped roof sections
CONFIDENCE	66%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

ROOF CONDITION BREAKDOWN

Membrane Condition		62/100
Ponding		58/100
Flashing & Seals		57/100
Penetrations		54/100
Overall Maintenance		58/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. Multiple roof planes and transitions are present across the complex, increasing flashing complexity.
3. Bright white roof sections dominate the image and suggest reflective roof surfaces or coating.
4. A distinct localized stain/discoloration is visible on the west side of the main roof mass.
5. Rooftop equipment/curbs and other small rooftop details appear on the central/right sections.

BUILDING CHARACTERISTICS

LAND AREA	8.50 acres
STORIES	1
CONSTRUCTION TYPE	Public
TAX DISTRICT	-
LAND VALUE	\$4,628,250

REPORT SUMMARY

This commercial property shows a mixed roof configuration with several low-slope white roof areas and multiple sloped roof sections. The visible roof surfaces appear generally serviceable, but localized discoloration, numerous transitions, rooftop details, and surrounding trees increase leak and maintenance risk. Aerial imagery alone does not confirm the roof membrane type, so the system is best treated as a probable single-ply or coated low-slope roof with other roof types also present. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Perform a closer rooftop inspection to verify membrane type, check the stained west-side area for moisture or prior repair history, review all flashings and penetrations, and clear/monitor nearby trees and debris. If not recently inspected, evaluate drainage performance and sealant condition at roof transitions and equipment curbs. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,040,982	Tear Off & Disposal	\$126,728
	Roof Membrane	\$253,456
	Insulation	\$153,884
	Flashing/Edging	\$99,572
	Labor	\$271,560
	Replacement Subtotal	\$905,202
	Contingency (15%)	\$135,780
	Total Project Cost	\$1,040,982

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$396,257	Overlay Subtotal	\$360,233
	Contingency (10%)	\$36,023
	Total Project Cost	\$396,257

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.