

250 S ROUTT ST

LAKEWOOD CO 80228

PROPERTY TYPE
Commercial 2130 2230

YEAR BUILT
-

BUILDING AREA
25,028 SF

ROOF SQUARES
250

PARCEL ID
4908401015



OVERALL ROOF CONDITION SCORE

72 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	single-ply membrane roof (exact chemistry not confirmed from aerial imagery)
POSSIBLE TYPES	TPO/PVC (58%); coating over membrane (36%); modified bitumen (24%)
VISIBLE CONCERNS	many penetrations/units; Multiple rooftop units, vents, and curbs are visible, increasing flashing and seal maintenance needs.; Roof surface appears generally uniform with no obvious widespread staining or ponding from this aerial view.
ROOF AGE EST.	apparent mid-life to older commercial roof; exact age not determinable from imagery alone
ROOF AREA	25,028 SF
ROOF PITCH	low-slope / near-flat

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

ROOF CONDITION BREAKDOWN

Membrane Condition		74/100
Ponding		78/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		69/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include high penetration or rooftop-unit density.
2. Large low-slope commercial roof with multiple stepped sections and parapet conditions.
3. Several rooftop mechanical units/vents/curbs are visible on the main roof areas.
4. Roof membrane appears light-colored and fairly uniform overall.
5. No obvious severe puncture damage, open tears, or major debris accumulation is visible from this imagery.

BUILDING CHARACTERISTICS

LAND AREA	12.77 acres
STORIES	-
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$4,448,640

REPORT SUMMARY

The aerial imagery shows a low-slope commercial roof with a generally uniform light-colored surface and no clear signs of major ponding or widespread discoloration. Visible rooftop equipment, vents, and roof transitions create moderate leak-risk points, so the roof appears serviceable but should be considered fair rather than excellent based on aerial-only evidence. Visible risk factors include high penetration or rooftop-unit density.

Recommendation:

Continue routine maintenance and inspect flashing, seals, and penetrations around rooftop units, curbs, and transitions. Monitor for localized wear or future ponding after heavy rain, and verify current roof condition with a close-up field inspection, since aerial imagery cannot confirm seam integrity or subsurface moisture.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$654,795	Tear Off & Disposal	\$79,714
	Roof Membrane	\$159,428
	Insulation	\$96,796
	Flashing/Edging	\$62,633
	Labor	\$170,816
\$22.75 / SF	Replacement Subtotal	\$569,387
	Contingency (15%)	\$85,408
	Total Project Cost	\$654,795

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$254,660	Overlay Subtotal	\$231,509
	Contingency (10%)	\$23,151
\$9.25 / SF	Total Project Cost	\$254,660

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.