

12043 W ALAMEDA PKWY

LAKEWOOD CO 80228

PROPERTY TYPE
Commercial 2112

YEAR BUILT
-

BUILDING AREA
75,951 SF

ROOF SQUARES
760

PARCEL ID
4917105011



OVERALL ROOF CONDITION SCORE

67 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	coated or white single-ply membrane over a large low-slope section, with darker adjacent roof areas that may be membrane or metal
POSSIBLE TYPES	TPO/PVC (68%); Coated membrane (61%); Metal (47%)
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Noticeable dark discoloration and uneven tonal areas on portions of the roof suggest prior repairs, staining, or localized weathering.
ROOF AGE EST.	Unknown from imagery; roof appears mixed-age or partially re-covered based on contrasting roof sections
ROOF AREA	75,951 SF
ROOF PITCH	Low-slope / near-flat
CONFIDENCE	74%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

ROOF CONDITION BREAKDOWN

Membrane Condition		66/100
Ponding		72/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		63/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.
2. The building has a large low-slope commercial roof with a bright white central field and darker adjoining roof areas.
3. Visible rooftop penetrations include vents, small mechanical units, and several curb-like details.
4. The roof surface is generally intact from aerial view, but several dark spots and localized discoloration are visible.
5. No obvious large open tears or severe widespread membrane failure are visible in this image.

BUILDING CHARACTERISTICS

LAND AREA	8.26 acres
STORIES	-
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$4,498,025

REPORT SUMMARY

Aerial imagery shows a large commercial low-slope roof with a reflective white roof field and adjacent darker roof sections. The roof appears serviceable overall, but visible discoloration, mixed roof areas, and multiple penetrations increase maintenance and leak-risk concerns. The exact membrane type cannot be confirmed from aerial imagery alone, though a reflective single-ply or coated membrane is a plausible candidate for the main bright roof area. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.

Recommendation:

Recommend a closer field inspection of the roof surface, penetrations, and transitions between roof sections, with particular attention to stained/discolored areas and flashing condition. Verify drainage performance, check for concealed ponding-related deterioration, and inspect any patched or coated areas for adhesion and watertightness.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$2,052,576	Tear Off & Disposal	\$249,879
	Roof Membrane	\$499,758
	Insulation	\$303,424
	Flashing/Edging	\$196,333
	Labor	\$535,455
	Replacement Subtotal	\$1,784,848
	Contingency (15%)	\$267,727
	Total Project Cost	\$2,052,576

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$793,688	Overlay Subtotal	\$721,534
	Contingency (10%)	\$72,153
	Total Project Cost	\$793,688

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.