

12364 W ALAMEDA PKWY

LAKEWOOD CO 80228

PROPERTY TYPE
Commercial Shopping Center, Neighbo...

YEAR BUILT
1971

BUILDING AREA
61,419 SF

ROOF SQUARES
614

PARCEL ID
4917406019



OVERALL ROOF CONDITION SCORE

67 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	likely coated low-slope membrane roof
POSSIBLE TYPES	TPO/PVC (54%); EPDM (42%); modified bitumen (38%)
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Noticeable mottled discoloration and darker streaking across portions of the roof field.
ROOF AGE EST.	appears mid-life to older commercial roof; building year built 1971 suggests an aging roof asset, but aerial imagery alone cannot determine install date
ROOF AREA	61,419 SF
ROOF PITCH	very low-slope / near-flat
CONFIDENCE	71%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

ROOF CONDITION BREAKDOWN

Membrane Condition		68/100
Ponding		68/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		66/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.
2. Commercial shopping center with multiple adjoining flat roof sections.
3. Roof surface is generally intact from aerial view with no obvious large blow-offs or open membrane tears visible.
4. Several rooftop penetrations and small rooftop units/vents are distributed across the roof planes.
5. Light-colored roof surfaces show scattered dark spots and uneven coloration, especially on the larger right-hand section.

BUILDING CHARACTERISTICS

LAND AREA	9.19 acres
STORIES	1
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$4,001,220

REPORT SUMMARY

This is a low-slope commercial roof with a generally serviceable appearance, but visible mottled staining, localized discoloration, and multiple penetrations indicate moderate service and leak-management risk. The roof may be a coated membrane or other single-ply low-slope system, but aerial imagery does not allow precise membrane identification. Overall condition reads as fair rather than good because the visible field staining and appurtenances suggest ongoing maintenance and flashing vigilance are important. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.

Recommendation:

Inspect the roof in person to confirm membrane type, evaluate stained/discolored areas, check flashing at all penetrations and curbs, and verify drainage performance. Consider targeted leak testing or moisture survey in areas with the heaviest discoloration. Reinspect after major weather events and maintain a regular sealant/flashing maintenance program. Field inspection should verify drainage, moisture, penetrations, flashing, and debris-related damage.

ROOF REPLACEMENT COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$1,659,848	Tear Off & Disposal	\$202,069
	Roof Membrane	\$404,137
	Insulation	\$245,369
	Flashing/Edging	\$158,768
	Labor	\$433,004
	Replacement Subtotal	\$1,443,346
	Contingency (15%)	\$216,502
	Total Project Cost	\$1,659,848

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

ROOF OVERLAY COST ESTIMATE

TOTAL PROJECT COST	COST COMPONENT	COST
\$641,829	Overlay Subtotal	\$583,480
	Contingency (10%)	\$58,348
	Total Project Cost	\$641,829

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.