

## 13175 W GREEN MOUNTAIN DR

LAKEWOOD CO 80228

PROPERTY TYPE

Public School, Entire Elementary...

YEAR BUILT

1973

BUILDING AREA

124,596 SF

ROOF SQUARES

1,246

PARCEL ID

492020001



OVERALL ROOF CONDITION SCORE

**72** /100  
FAIR

RISK LEVEL

MODERATE



### ROOF INFORMATION

|                  |                                                                                                                                                                                       |
|------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ROOF TYPE        | low-slope / flat commercial roof                                                                                                                                                      |
| ROOF SYSTEM      | single-ply or coated low-slope membrane (exact chemistry not discernible from aerial imagery)                                                                                         |
| POSSIBLE TYPES   | TPO/PVC (58%); EPDM (35%); Modified bitumen (30%)                                                                                                                                     |
| VISIBLE CONCERNS | dark staining/color variation; many penetrations/units; tree/debris exposure                                                                                                          |
| ROOF AGE EST.    | Likely original/long-service roof with repeated maintenance; exact age not determinable from imagery alone. Building year built 1973 suggests an older roof assembly unless replaced. |
| ROOF AREA        | 124,596 SF                                                                                                                                                                            |
| ROOF PITCH       | low-slope / near-flat                                                                                                                                                                 |
| CONFIDENCE       | 71%                                                                                                                                                                                   |

### SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

### ROOF CONDITION BREAKDOWN

|                     |                        |        |
|---------------------|------------------------|--------|
| Membrane Condition  | <div><div></div></div> | 68/100 |
| Ponding             | <div><div></div></div> | 72/100 |
| Flashing & Seals    | <div><div></div></div> | 64/100 |
| Penetrations        | <div><div></div></div> | 58/100 |
| Overall Maintenance | <div><div></div></div> | 62/100 |

### AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. The complex consists of multiple connected low-slope roof sections with parapets and many rooftop penetrations.
3. Roof surface appears generally serviceable and intact from this altitude, with no obvious catastrophic membrane failure.
4. Color variation and localized darker patches are visible on several sections, especially near edges and around roof features.
5. The site has substantial tree coverage adjacent to the roof perimeter, which may contribute organic debris to roof drains and edges.

### BUILDING CHARACTERISTICS

|                   |             |
|-------------------|-------------|
| LAND AREA         | 29.75 acres |
| STORIES           | 1           |
| CONSTRUCTION TYPE | Public      |
| TAX DISTRICT      | -           |
| LAND VALUE        | \$1,487,545 |

### REPORT SUMMARY

The aerial image shows a large, older low-slope school roof system that appears generally intact but actively maintained. Visible roof color variation, darker stained areas, and many penetrations lower confidence in long-term watertight performance. Tree adjacency adds debris and maintenance risk. Exact membrane type cannot be confirmed from overhead imagery, but the roof is most consistent with a single-ply or coated low-slope membrane. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

#### Recommendation:

Recommend a closer roof inspection focused on seams, flashings, penetrations, drains, and the darker-discolored roof areas. Check for signs of prior repairs, trapped moisture, or recurring drainage issues. If this is an older membrane, consider documenting remaining service life and planning for maintenance or targeted restoration based on field inspection findings.

### ROOF REPLACEMENT COST ESTIMATE

| TOTAL PROJECT COST  | COST COMPONENT              | COST               |
|---------------------|-----------------------------|--------------------|
| <b>\$3,259,743</b>  | Tear Off & Disposal         | \$396,838          |
|                     | Roof Membrane               | \$793,677          |
|                     | Insulation                  | \$481,875          |
|                     | Flashing/Edging             | \$311,801          |
|                     | Labor                       | \$850,368          |
| <b>\$22.75 / SF</b> | <b>Replacement Subtotal</b> | <b>\$2,834,559</b> |
|                     | <b>Contingency (15%)</b>    | <b>\$425,184</b>   |
|                     | <b>Total Project Cost</b>   | <b>\$3,259,743</b> |

This replacement cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.

### ROOF OVERLAY COST ESTIMATE

| TOTAL PROJECT COST | COST COMPONENT            | COST               |
|--------------------|---------------------------|--------------------|
| <b>\$1,267,764</b> | <b>Overlay Subtotal</b>   | <b>\$1,152,513</b> |
|                    | <b>Contingency (10%)</b>  | <b>\$115,251</b>   |
| <b>\$9.25 / SF</b> | <b>Total Project Cost</b> | <b>\$1,267,764</b> |

This overlay cost is an estimate derived from aerial imagery, public property records, and commercial roofing cost models. It is intended for budgeting purposes only and should not be considered a contractor quote or engineering assessment.