

4201 E 72ND AVE

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Government Building

YEAR BUILT

-

BUILDING AREA

10,856 SF

ROOF SQUARES

109

PARCEL ID

0172131300018



OVERALL ROOF CONDITION SCORE

68 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Mixed roof types
ROOF SYSTEM	Primary: Ballasted
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; tree/debris exposure
ROOF AGE EST.	Appears mature/older in aerial appearance; exact age unknown. The 11/13/2025 imagery shows weathered aggregate and multiple rooftop penetrations, but age cannot be determined from imagery alone.
ROOF AREA	10,856 SF
ROOF PITCH	Low-slope/flat
CONFIDENCE	86%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		68/100
Ponding		66/100
Flashing & Seals		64/100
Penetrations		58/100
Overall Maintenance		62/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. Main roof field is a continuous tan/brown aggregate-surfaced low-slope assembly.
3. Several attached smaller roof sections are visible, including a rounded southern/western addition and smaller connector areas, and they appear to share the same aggregate surface or transition into smoother low-slope material.
4. Rooftop equipment, vents, and curbs are numerous across the roof, creating multiple flashing and seal points.
5. Perimeter and transition lines are visible, but seam or lap detail is not sufficiently resolved to confirm a specific hidden membrane beneath the aggregate.

BUILDING CHARACTERISTICS

LAND AREA	2.08 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

Esri World Imagery dated 11/13/2025 shows a commercial government building with a predominantly ballasted or gravel-surfaced low-slope roof and smaller attached roof sections of similar appearance. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Based on the visible aerial evidence, this roof should be treated as a mixed low-slope assembly with a dominant aggregate-surfaced roof and smaller attached sections that may be membrane or coated membrane. A qualified commercial roof-coating contractor should perform an onsite inspection, moisture testing where warranted, confirmation of the visible roof system and warranty eligibility, required repairs and preparation, and a reliable project-price proposal. If the aggregate-surfaced areas are structurally sound and moisture is not widespread, evaluate whether a silicone roof restoration system could be a cost-effective option before overlay or replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, improve resistance to UV exposure and hail, withstand ponding water when properly designed and installed, and qualify for a manufacturer's 0

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$293,383

\$23.50 / SF

COST SUMMARY

Replacement Subtotal	\$255,116
Contingency (15%)	\$38,267
Total Project Cost	\$293,383

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$113,445

\$9.50 / SF

COST SUMMARY

Overlay Subtotal	\$103,132
Contingency (10%)	\$10,313
Total Project Cost	\$113,445

Roof Coating Estimate

TOTAL PROJECT COST

\$37,996 - \$65,136

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$37,996 - \$43,424
15 Year Warranty	\$48,852 - \$54,280
20 Year Warranty	\$59,708 - \$65,136

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.