

7200 QUEBEC PKWY

COMMERCE CITY CO 80022

PROPERTY TYPE

Commercial School - Elementary/Seco...

YEAR BUILT

-

BUILDING AREA

36,921 SF

ROOF SQUARES

369

PARCEL ID

0172133301001



OVERALL ROOF CONDITION SCORE

62 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Mixed roof types
ROOF SYSTEM	Primary: TPO; Secondary: Metal
VISIBLE CONCERNS	dark staining/color variation; possible ponding; many penetrations/units; tree/debris exposure
ROOF AGE EST.	Unknown from aerial imagery; overall appears to be a combination of newer-looking bright membrane fields and distinct panelized roof sections, but exact installation dates cannot be confirmed.
ROOF AREA	36,921 SF
ROOF PITCH	Predominantly low-slope with some steeper/panelized roof planes
CONFIDENCE	82%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		62/100
Ponding		55/100
Flashing & Seals		63/100
Penetrations		58/100
Overall Maintenance		61/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. The building is clearly mixed-roof based on visible panelized sections and broad white membrane-like roof fields.
3. Northwest upper roof blocks show strong metal cues: rigid panel geometry, repeated seams, and directional reflectance.
4. Most large roof fields read as bright smooth low-slope membrane surfaces, but exact chemistry cannot be confirmed from aerial imagery alone.
5. Multiple rooftop units, vents, and curbs are distributed across the roof, creating many flashing points.

BUILDING CHARACTERISTICS

LAND AREA	8.60 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

Esri World Imagery dated 11/13/2025 shows a mixed-roof commercial school with distinct panelized metal roof sections and extensive bright low-slope membrane areas. Visible risk factors include dark staining or inconsistent roof color, possible ponding or drainage stress, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Recommend a qualified commercial roofing contractor perform an onsite inspection to confirm the visible roof systems, test for moisture where the stained or darker areas warrant it, and document flashing, drainage, and penetration conditions. For the apparently restorable low-slope membrane areas, also evaluate a silicone roof restoration system before considering a more costly overlay or replacement; a qualifying silicone system can potentially reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water when properly designed and installed, improve resistance to UV. A qualified commercial roof-coating contractor should perform an onsite inspection, complete moisture testing when warranted, verify drainage, moisture, penetrations, flashing, and debris-related damage, confirm silicone-system and warranty eligibility, and provide a reliable project-price proposal.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$1,040,249

\$24.50 / SF

COST SUMMARY

Replacement Subtotal **\$904,564**

Contingency (15%) **\$135,685**

Total Project Cost **\$1,040,249**

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$395,978

\$9.75 / SF

COST SUMMARY

Overlay Subtotal **\$359,980**

Contingency (10%) **\$35,998**

Total Project Cost **\$395,978**

Roof Coating Estimate

TOTAL PROJECT COST

\$129,224 - \$221,526

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty **\$129,224 - \$147,684**

15 Year Warranty **\$166,144 - \$184,605**

20 Year Warranty **\$203,066 - \$221,526**

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.