

5101 QUEBEC ST

COMMERCE CITY CO 80022

PROPERTY TYPE
Commercial Truck Stop Restaurant

YEAR BUILT

-

BUILDING AREA

5,853 SF

ROOF SQUARES

59

PARCEL ID

0182317107020



OVERALL ROOF CONDITION SCORE

64 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	Mixed roof types
ROOF SYSTEM	Primary: TPO; Secondary: Metal
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Localized dark discoloration and patchy staining are visible on portions of the white roof field.
ROOF AGE EST.	Likely moderate to older low-slope roof segments overall; the white field appears maintained, while the gray attached section shows more weathering. Exact age cannot be determined from aerial imagery alone.
ROOF AREA	5,853 SF
ROOF PITCH	Low-slope / flat
CONFIDENCE	72%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY AS OF 11/13/2025

ROOF CONDITION BREAKDOWN

Membrane Condition		61/100
Ponding		60/100
Flashing & Seals		58/100
Penetrations		56/100
Overall Maintenance		62/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.
2. Main roof field is a large bright white/light low-slope membrane-like surface with smooth appearance.
3. Several rooftop units, vents, curbs, and small penetrations are visible across the main roof field.
4. Localized dark spots and uneven discoloration are visible on the white roof, suggesting staining, repairs, or possible drainage-related wear.
5. A smaller attached left-lower gray rectangular section appears materially different and more weathered than the main white field.

BUILDING CHARACTERISTICS

LAND AREA	4.17 acres
STORIES	-
CONSTRUCTION TYPE	-
TAX DISTRICT	-
LAND VALUE	-

REPORT SUMMARY

Aerial imagery dated 11/13/2025 shows a mixed commercial roof at 5101 Quebec St, Commerce City, with a dominant smooth white/light low-slope membrane-like field and smaller distinct roof areas. The main roof presents localized dark staining/discoloration and many rooftop penetrations and curbs, which increase leak potential and flashing risk. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density.

Recommendation:

Have a qualified commercial roof-coating contractor perform an onsite inspection to confirm the roof system, assess seams, flashings, penetrations, and any wet-insulation indicators, and determine whether moisture testing is warranted. If the white low-slope field is serviceable and not showing widespread moisture or substrate failure, evaluate silicone roof restoration as a potential option before a more costly overlay or replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water when properly designed and installed, improve resistance to UV exposure and hail, and qualify for a manufacturer warranty of up to 20 years. If inspection finds widespread moisture, failed insulation, incompatible substrate, or deterioration beyond restoration, evaluate overlay or replacement instead. Confirm system eligibility, required pre

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$164,908	Replacement Subtotal \$143,398
\$24.50 / SF	Contingency (15%) \$21,510
	Total Project Cost \$164,908

Roof Overlay Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$62,773	Overlay Subtotal \$57,067
\$9.75 / SF	Contingency (10%) \$5,707
	Total Project Cost \$62,773

Roof Coating Estimate

TOTAL PROJECT COST	WARRANTY TERM	BUDGETARY COST RANGE
\$20,486 - \$35,118	10 Year Warranty	\$20,486 - \$23,412
\$3.50 - \$6.00 / SF	15 Year Warranty	\$26,338 - \$29,265
	20 Year Warranty	\$32,192 - \$35,118

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.