

12364 W ALAMEDA PKWY

LAKEWOOD CO 80228

PROPERTY TYPE
Commercial Shopping Center, Neighbo...

YEAR BUILT
1971

BUILDING AREA
61,419 SF

ROOF SQUARES
614

PARCEL ID
4917406019



OVERALL ROOF CONDITION SCORE

56 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Mixed roof types
ROOF SYSTEM	Primary: TPO
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; tree/debris exposure
ROOF AGE EST.	Likely older low-slope commercial roof, consistent with a 1971-built shopping center; visible weathering suggests mid-to-late service life, but exact age cannot be determined from aerial imagery.
ROOF AREA	61,419 SF
ROOF PITCH	Low-slope / flat
CONFIDENCE	60%

SELECTED AERIAL IMAGE - ESRI WORLD IMAGERY

ROOF CONDITION BREAKDOWN

Membrane Condition		56/100
Ponding		58/100
Flashing & Seals		52/100
Penetrations		50/100
Overall Maintenance		54/100

AERIAL ROOF OBSERVATIONS

1. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.
2. The building appears to have multiple materially different roof zones rather than one uniform roof system.
3. West and east main roof blocks are light-colored, smooth, and membrane-like, with seams too soft to confirm exact chemistry from aerial imagery.
4. The center connector/courtyard-adjacent section is smaller, tan/beige, and more asphaltic-weathered in appearance than the main fields.
5. Numerous rooftop penetrations and equipment units are visible across the roof, increasing flashing and seal risk.

BUILDING CHARACTERISTICS

LAND AREA	9.19 acres
STORIES	1
CONSTRUCTION TYPE	Commercial
TAX DISTRICT	-
LAND VALUE	\$4,001,220

REPORT SUMMARY

Aerial imagery shows a mixed low-slope commercial roof at this 1971 shopping center, with large light membrane-like roof fields and a smaller tan weathered connector section. Visible risk factors include dark staining or inconsistent roof color, high penetration or rooftop-unit density, tree overhang or roof debris exposure.

Recommendation:

Have a qualified commercial roof-coating contractor perform an onsite inspection, including moisture testing where warranted, to confirm the roof systems, repairs, and warranty eligibility. If the white low-slope sections are otherwise sound and restorable, evaluate silicone roof restoration before overlay or replacement because a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water when properly designed and installed, improve UV and hail resistance, and may qualify for a manufacturer warranty of up to 20 years. If inspection finds widespread moisture, failed insulation, substrate incompatibility, or deterioration beyond restoration, pursue overlay or replacement evaluation instead.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$1,801,112	Replacement Subtotal \$1,566,184
\$25.50 / SF	Contingency (15%) \$234,928
	Total Project Cost \$1,801,112

Roof Overlay Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$675,609	Overlay Subtotal \$614,190
\$10.00 / SF	Contingency (10%) \$61,419
	Total Project Cost \$675,609

Roof Coating Estimate

TOTAL PROJECT COST	WARRANTY TERM	BUDGETARY COST RANGE
\$214,966 - \$368,514	10 Year Warranty	\$214,966 - \$245,676
\$3.50 - \$6.00 / SF	15 Year Warranty	\$276,386 - \$307,095
	20 Year Warranty	\$337,804 - \$368,514

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.