

4301 N FOREST ST

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-FOOD PROCESSING 391: FOO...

YEAR BUILT
1969

BUILDING AREA
76,458 SF

ROOF SQUARES
765

PARCEL ID
0119100091000



OVERALL ROOF CONDITION SCORE

58 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof
ROOF SYSTEM	Primary: Likely ballasted membrane or modified bitumen roof field with a uniform tan weathered surface; exact chemistry is not fully discernible from aerial imagery.
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Several small darkened spots and localized discoloration are visible on the roof field.
ROOF AGE EST.	Appears older and service-aged, consistent with a roof on a 1969 industrial building; exact age cannot be confirmed from aerial imagery.
ROOF AREA	76,458 SF
ROOF PITCH	Low-slope
CONFIDENCE	67%

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		55/100
Ponding		62/100
Flashing & Seals		52/100
Penetrations		50/100
Overall Maintenance		54/100

AERIAL ROOF OBSERVATIONS

1. Large low-slope industrial roof footprint with multiple connected roof sections.
2. Roof surface is generally uniform but shows scattered dark spots and localized discoloration.
3. Numerous penetrations, vents, curbs, and rooftop equipment are visible across multiple roof areas.
4. Perimeter and step transitions create additional flashing interfaces.
5. Visible roof appearance suggests serviceable but aging conditions rather than acute failure.

BUILDING CHARACTERISTICS

LAND AREA	6.59 acres
STORIES	-
CONSTRUCTION TYPE	391: FOOD PRCSNG/COLD ST
TAX DISTRICT	DENV
LAND VALUE	\$3,012,800

REPORT SUMMARY

Aerial imagery dated 03/11/2018 - 03/17/2018 shows a large low-slope commercial roof at 4301 N FOREST ST with generally uniform appearance but scattered dark staining/discoloration and multiple rooftop penetrations, vents, and equipment curbs. The roof appears service-aged and moderate risk, with leak potential driven more by flashing/penetration complexity and localized discoloration than by obvious severe distress. Older imagery may understate current deterioration.

Recommendation:

Have a qualified commercial roofing contractor perform an onsite inspection, including moisture testing if warranted, to confirm the roof system, evaluate the darkened areas for staining versus trapped moisture or leak impact, and assess flashing/seal conditions around penetrations and transitions. If the roof is still broadly serviceable and not a shingle substrate, evaluate silicone roof restoration as a potential option before a more costly overlay or replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, improve resistance to UV exposure and hail, withstand ponding water when properly designed and installed, and may qualify for a manufacturer warranty of up to 20 years. If onsite findings show widespread moisture, failed insulation, substrate incompatibility, or other advanced deterioration, pursue overlay or replacement evaluation.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$2,242,131	Replacement Subtotal \$1,949,679
\$25.50 / SF	Contingency (15%) \$292,452
	Total Project Cost \$2,242,131

Roof Overlay Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$841,038	Overlay Subtotal \$764,580
\$10.00 / SF	Contingency (10%) \$76,458
	Total Project Cost \$841,038

Roof Coating Estimate

TOTAL PROJECT COST	WARRANTY TERM	BUDGETARY COST RANGE
\$267,603 - \$458,748	10 Year Warranty	\$267,603 - \$305,832
\$3.50 - \$6.00 / SF	15 Year Warranty	\$344,061 - \$382,290
	20 Year Warranty	\$420,519 - \$458,748

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.