

4360 N DAHLIA ST

DENVER CO 80216

PROPERTY TYPE

INDUSTRIAL-WAREHOUSE 391: FOOD PRC...

YEAR BUILT

1972

BUILDING AREA

182,615 SF

ROOF SQUARES

1,826

PARCEL ID

0119100094000



OVERALL ROOF CONDITION SCORE

55 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial/industrial roof
ROOF SYSTEM	Primary: Predominantly smooth low-slope membrane roof, likely built-up or modified bitumen, with a separate smooth low-slope field that may be a coated membrane
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Several darkened roof areas and tonal variation are visible across the large left roof field, which may reflect weathering, staining, or prior repairs.
ROOF AGE EST.	Likely original or older low-slope commercial roofing, with visible materials and layout consistent with an aging roof from the building era; exact age not determinable from aerial imagery alone.
ROOF AREA	182,615 SF
ROOF PITCH	Very low-slope / flat

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		53/100
Ponding		58/100
Flashing & Seals		52/100
Penetrations		48/100
Overall Maintenance		54/100

AERIAL ROOF OBSERVATIONS

1. Large industrial warehouse complex with extensive low-slope roof area.
2. Left roof field shows many evenly spaced skylights/penetrations and multiple rooftop appurtenances.
3. Darkened patches and uneven coloration are visible on the left roof field, especially near seams and across broad areas.
4. Right roof field appears more uniform and lighter in color, possibly a coated or newer membrane field.
5. Perimeter edges and transitions show multiple flashing conditions, but fine-detail seal condition cannot be confirmed from aerial imagery.

BUILDING CHARACTERISTICS

LAND AREA	10.09 acres
STORIES	-
CONSTRUCTION TYPE	391: FOOD PRCSNG/COLD ST
TAX DISTRICT	DENV
LAND VALUE	\$4,615,900

REPORT SUMMARY

Aerial imagery dated 03/11/2018 - 03/17/2018 shows a large low-slope commercial roof complex in poor current-likely condition with moderate serviceability risk. The roof appears to be a smooth membrane or bituminous system, with one field showing broad dark discoloration and tonal variation that may indicate weathering, prior repairs, or moisture-related staining. Numerous skylights, vents, and rooftop units increase flashing and leak potential. No clear tree overhang or debris buildup

Recommendation:

Have a qualified commercial roof-coating contractor perform an onsite inspection and moisture testing where warranted to confirm the roof system, identify required repairs, and verify restoration eligibility. If the substrate is sound and the roof is otherwise suitable, evaluate a silicone roof restoration before a more costly overlay or replacement; a properly designed silicone system can reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water when properly installed, improve UV and hail resistance, and may qualify for a manufacturer warranty of up to 20 years. If onsite findings show widespread moisture, failed insulation, incompatible substrate, or advanced deterioration, then an overlay or replacement evaluation is more appropriate.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$5,355,185

\$25.50 / SF

COST SUMMARY

Replacement Subtotal	\$4,656,682
Contingency (15%)	\$698,502
Total Project Cost	\$5,355,185

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$2,058,984

\$10.25 / SF

COST SUMMARY

Overlay Subtotal	\$1,871,804
Contingency (10%)	\$187,180
Total Project Cost	\$2,058,984

Roof Coating Estimate

TOTAL PROJECT COST

\$639,152 - \$1,095,690

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$639,152 - \$730,460
15 Year Warranty	\$821,768 - \$913,075
20 Year Warranty	\$1,004,382 - \$1,095,690

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.