

4275 N FOREST ST

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 397: OFFICE/WA...

YEAR BUILT
1969

BUILDING AREA
32,095 SF

ROOF SQUARES
321

PARCEL ID
0119100095000



OVERALL ROOF CONDITION SCORE

59 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof
ROOF SYSTEM	Primary: Predominantly membrane roof with a separate darker low-slope field; primary field appears to be coated membrane or thermoplastic membrane, with an adjacent darker membrane section of uncertain type.
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Visible darkened roof field contrasts strongly with the adjacent lighter roof areas, suggesting a distinct membrane section or possible coating/weathering pattern.
ROOF AGE EST.	Likely original-era or older low-slope roof components consistent with a 1969 industrial building, though aerial imagery cannot confirm install date.
ROOF AREA	32,095 SF
ROOF PITCH	Low-slope / near-flat

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		61/100
Ponding		59/100
Flashing & Seals		53/100
Penetrations		50/100
Overall Maintenance		56/100

AERIAL ROOF OBSERVATIONS

1. Industrial warehouse building with multiple low-slope roof sections.
2. One large central dark roof field is visibly distinct from the surrounding lighter roof surfaces.
3. Several vents, curbs, and rooftop units/penetrations are present on the roof.
4. Roof surfaces appear generally serviceable from aerial view, but the tonal contrast suggests maintenance or aging differences between sections.
5. No obvious tree overhang or major debris accumulation is visible at the roof edges.

BUILDING CHARACTERISTICS

LAND AREA	3.62 acres
STORIES	-
CONSTRUCTION TYPE	397: OFFICE/WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$2,131,600

REPORT SUMMARY

Aerial imagery dated 03/11/2018 - 03/17/2018 shows a low-slope industrial roof with multiple membrane fields, including a large darker section and lighter weathered sections that may indicate different roof materials, coating, or age-related discoloration. Visible penetrations and rooftop equipment increase flashing and leak potential. No clear ponding or heavy debris is evident, but the roof presents moderate serviceability risk and the older imagery may understate more

Recommendation:

Have a qualified commercial roof-coating contractor perform an onsite inspection and moisture testing where warranted, confirm the actual roof system and warranty eligibility, identify required repairs and surface preparation, and provide a reliable project-price proposal. If the roof is a suitable low-slope membrane in restorable condition, evaluate a silicone roof restoration option before overlay or replacement; when properly designed and installed, a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water, improve UV and hail resistance, and qualify for a manufacturer warranty of up to 20 years. If onsite findings show widespread moisture, failed insulation, deck or structural deterioration, incompatible substrate, or other non-restorable conditions, evaluate overlay or full replacement instead.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$941,186	Replacement Subtotal \$818,422
\$25.50 / SF	Contingency (15%) \$122,763
	Total Project Cost \$941,186

Roof Overlay Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$353,045	Overlay Subtotal \$320,950
\$10.00 / SF	Contingency (10%) \$32,095
	Total Project Cost \$353,045

Roof Coating Estimate

TOTAL PROJECT COST	WARRANTY TERM	BUDGETARY COST RANGE
\$112,332 - \$192,570	10 Year Warranty	\$112,332 - \$128,380
\$3.50 - \$6.00 / SF	15 Year Warranty	\$144,428 - \$160,475
	20 Year Warranty	\$176,522 - \$192,570

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.