

4500 N DAHLIA ST

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 398: WAREHOU...

YEAR BUILT
1973

BUILDING AREA
124,974 SF

ROOF SQUARES
1,250

PARCEL ID
0119100103000



SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

OVERALL ROOF CONDITION SCORE

50 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial warehouse roof
ROOF SYSTEM	Primary: Primarily low-slope membrane roof; exact membrane type not fully resolvable from aerial imagery alone. Large flat roof fields appear consistent with a single-ply or coated membrane assembly over an industrial warehouse.
VISIBLE CONCERNS	dark staining/color variation; possible ponding; many penetrations/units
ROOF AGE EST.	Likely older low-slope commercial roof, consistent with a 1973 industrial warehouse; visible roof field suggests a service-aged system, but precise installation age is not discernible from aerial imagery.
ROOF AREA	124,974 SF
ROOF PITCH	Flat to very low-slope

ROOF CONDITION BREAKDOWN

Membrane Condition		52/100
Ponding		47/100
Flashing & Seals		44/100
Penetrations		42/100
Overall Maintenance		48/100

AERIAL ROOF OBSERVATIONS

1. Large industrial warehouse with extensive flat roof area and multiple distinct roof sections.
2. Numerous rooftop penetrations, curbs, vents, and mechanical units are present across the roof field.
3. Visible darker staining/discoloration and uneven roof coloration occur in several areas.
4. No clear signs of severe membrane failure, open tears, or large exposed substrate are visible from the aerial view.
5. Image resolution does not allow reliable identification of exact membrane chemistry or hidden wet insulation conditions.

BUILDING CHARACTERISTICS

LAND AREA	7.70 acres
STORIES	-
CONSTRUCTION TYPE	398: WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$3,520,000

REPORT SUMMARY

Aerial imagery from 03/11/2018 - 03/17/2018 shows a large low-slope industrial warehouse roof in poor current-likely condition with moderate serviceability risk. The roof appears to be a broad membrane-type assembly, but exact material cannot be confirmed from the aerial view. Visible dark staining/discoloration and uneven color patterns suggest possible ponding history, localized moisture retention, or prior repairs. The roof also has many penetrations, curbs, vents, and mechanical/ro

Recommendation:

Have a qualified commercial roofing contractor perform an onsite inspection with moisture testing where warranted, verify the membrane type and flashing condition, and estimate repair scope and project pricing. If the roof is generally sound and restoration-compatible, evaluate silicone roof restoration before a more costly overlay or replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, withstand ponding water when properly designed and installed, improve resistance to UV exposure and hail, and may qualify for a manufacturer warranty of up to 20 years. If field testing shows widespread moisture, failed insulation, structural/deck deterioration, or an incompatible substrate, pursue overlay or replacement evaluation instead.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$3,844,513

\$26.75 / SF

COST SUMMARY

Replacement Subtotal	\$3,343,054
Contingency (15%)	\$501,458
Total Project Cost	\$3,844,513

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$1,443,450

\$10.50 / SF

COST SUMMARY

Overlay Subtotal	\$1,312,227
Contingency (10%)	\$131,223
Total Project Cost	\$1,443,450

Roof Coating Estimate

TOTAL PROJECT COST

\$437,409 - \$749,844

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$437,409 - \$499,896
15 Year Warranty	\$562,383 - \$624,870
20 Year Warranty	\$687,357 - \$749,844

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.