

5290 E 43RD AVE

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 398: WAREHOU...

YEAR BUILT
2017

BUILDING AREA
31,068 SF

ROOF SQUARES
311

PARCEL ID
0119400217000



OVERALL ROOF CONDITION SCORE

70 /100
FAIR

RISK LEVEL

MODERATE



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	Primary: Metal roof field with a separate lighter low-slope roof area; primary roof field appears to be metal panel roofing
VISIBLE CONCERNS	many penetrations/units; Several rooftop penetrations/equipment items are visible on the lighter roof area, increasing flashing and seal maintenance needs.; No obvious widespread staining, algae-like discoloration, or ponding is visible from this aerial image.
ROOF AGE EST.	Newer roof, likely within a few years of 2018 given the 2017 construction date and generally serviceable appearance
ROOF AREA	31,068 SF
ROOF PITCH	Low-slope to slightly pitched
CONFIDENCE	72%

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		72/100
Ponding		70/100
Flashing & Seals		64/100
Penetrations		60/100
Overall Maintenance		68/100

AERIAL ROOF OBSERVATIONS

1. The dominant roof surface shows repeated linear bands and reflective striping consistent with a metal panel roof field.
2. A separate lighter low-slope roof area is visible with a few penetrations/equipment items near the upper section.
3. No clear widespread membrane discoloration, dark staining, or debris accumulation is visible.
4. No obvious ponding areas are apparent from the overhead imagery.
5. Perimeter and adjacent site areas do not show overhanging trees contacting the roof.

BUILDING CHARACTERISTICS

LAND AREA	1.31 acres
STORIES	-
CONSTRUCTION TYPE	398: WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$853,000

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$812,817

\$22.75 / SF

COST SUMMARY

Replacement Subtotal	\$706,797
Contingency (15%)	\$106,020
Total Project Cost	\$812,817

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$324,661

\$9.50 / SF

COST SUMMARY

Overlay Subtotal	\$295,146
Contingency (10%)	\$29,515
Total Project Cost	\$324,661

Roof Coating Estimate

TOTAL PROJECT COST

\$108,738 - \$186,408

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$108,738 - \$124,272
15 Year Warranty	\$139,806 - \$155,340
20 Year Warranty	\$170,874 - \$186,408

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.

REPORT SUMMARY

Aerial imagery from 03/11/2018 - 03/17/2018 shows a generally serviceable industrial roof with a dominant metal roof field and a separate lighter low-slope roof area. Visible risk is mainly from the limited number of rooftop penetrations/equipment on the low-slope section, which increases flashing and seal vulnerability. No clear widespread staining, debris accumulation, or obvious ponding is visible in the image, though older imagery may understate current wear.

Recommendation:

The roof appears generally sound from aerial view, but the visible penetrations and low-slope areas warrant an onsite commercial roof inspection to confirm flashing, seams, and drainage performance. If the lighter low-slope section is a qualifying membrane roof and remains restorable, a silicone roof restoration could be evaluated before a more costly overlay or replacement, as a properly designed system may reduce tear-off waste, cost, and disruption while creating a seamless reflective surface and improving UV/ponding resistance; confirm system compatibility, moisture conditions, repairs, and warranty eligibility with a qualified commercial roof-coating contractor. If onsite inspection finds hidden moisture, substrate problems, or incompatible materials, then overlay or replacement evaluation would be more appropriate.