

4882 E SMITH RD

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 398: WAREHOU...

YEAR BUILT
1974

BUILDING AREA
18,151 SF

ROOF SQUARES
182

PARCEL ID
0119400252000



OVERALL ROOF CONDITION SCORE

52 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof
ROOF SYSTEM	Primary: Likely smooth single-ply membrane roof, possibly EPDM or TPO/PVC, with one lighter adjacent low-slope roof field that appears to be a separate membrane-coated/white roof surface
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Main roof field shows localized lighter/darker patches and small discoloration areas that may reflect repairs, staining, or drainage-related wear.
ROOF AGE EST.	Likely original or near-original to a building from 1974, though the visible roof surface may have been replaced or recoated later
ROOF AREA	18,151 SF
ROOF PITCH	Low-slope / near-flat

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		53/100
Ponding		54/100
Flashing & Seals		48/100
Penetrations		50/100
Overall Maintenance		52/100

AERIAL ROOF OBSERVATIONS

1. Main roof is a dark low-slope field with a fairly uniform membrane-like appearance.
2. Several small rooftop penetrations and equipment pads/curbs are visible across the roof.
3. Localized lighter patches and minor discoloration are visible on the main roof surface.
4. An adjacent lower roof field to the south appears much lighter/white and may be a different roof surface or a coated membrane.
5. Roof perimeter and parapet/edge details are visible but fine flashing condition cannot be confirmed from aerial imagery alone.

BUILDING CHARACTERISTICS

LAND AREA	0.72 acres
STORIES	-
CONSTRUCTION TYPE	398: WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$425,200

REPORT SUMMARY

Aerial imagery dated 03/11/2018 - 03/17/2018 shows a low-slope commercial roof with a dark main membrane field and an adjacent lighter low-slope roof area. The main roof appears generally serviceable but has localized discoloration/patchy areas and multiple roof penetrations, which increase leak and flashing-maintenance risk. No clear large ponding is visible, though drainage performance cannot be confirmed from this view. Overall condition appears fair with moderate low

Recommendation:

Have a qualified commercial roofing contractor perform an onsite inspection to confirm the roof system, evaluate flashing and penetration seals, and test for moisture if leaks or soft areas are suspected. If the roof is an apparently restorable low-slope membrane and not asphalt shingle, evaluate silicone roof restoration before a more costly overlay or full replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless monolithic white reflective cool-roof surface, improve resistance to UV exposure and hail, withstand ponding water when properly designed and installed, and may qualify for a manufacturer warranty of up to 20 years. If field testing shows widespread moisture, insulation failure, deck deterioration, or incompatible substrate conditions, an overlay or replacement evaluation is more appropriate. Confirm system eligibility, needed repairs, preparation scope, and project pricing.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$558,370

\$26.75 / SF

COST SUMMARY

Replacement Subtotal	\$485,539
Contingency (15%)	\$72,831
Total Project Cost	\$558,370

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$204,653

\$10.25 / SF

COST SUMMARY

Overlay Subtotal	\$186,048
Contingency (10%)	\$18,605
Total Project Cost	\$204,653

Roof Coating Estimate

TOTAL PROJECT COST

\$63,528 - \$108,906

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$63,528 - \$72,604
15 Year Warranty	\$81,680 - \$90,755
20 Year Warranty	\$99,830 - \$108,906

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.