

5105 E 41ST AVE

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 398: WAREHOU...

YEAR BUILT
1974

BUILDING AREA
77,226 SF

ROOF SQUARES
772

PARCEL ID
0119400262000



OVERALL ROOF CONDITION SCORE

50 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	Low-slope commercial roof
ROOF SYSTEM	Primary: Likely low-slope membrane roof with a smooth-coated or aged membrane surface; exact chemistry not discernible from aerial imagery alone
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Visible localized dark spots and scattered discoloration on the white roof field suggest prior repairs, weathering, or moisture-related staining potential.
ROOF AGE EST.	Likely original or near-original to a 1974 warehouse, though surface treatment/recoat history is unknown; aerial imagery alone cannot confirm age.
ROOF AREA	77,226 SF
ROOF PITCH	Flat to very low slope
CONFIDENCE	72%

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		52/100
Ponding		54/100
Flashing & Seals		48/100
Penetrations		44/100
Overall Maintenance		50/100

AERIAL ROOF OBSERVATIONS

1. Large low-slope commercial roof with multiple rooftop penetrations, vents, and small equipment curbs.
2. White roof field shows scattered dark speckling, spot staining, and uneven coloration.
3. Tan roof field appears more uniform but still has several visible penetrations.
4. Perimeter drainage details are not clearly readable from this overhead image.
5. Visible rooftop components increase seal and flashing vulnerability on an older industrial roof.

BUILDING CHARACTERISTICS

LAND AREA	3.54 acres
STORIES	-
CONSTRUCTION TYPE	398: WAREHOUSE
TAX DISTRICT	DENV
LAND VALUE	\$2,198,700

REPORT SUMMARY

03/11/2018 - 03/17/2018 Denver GIS aerial imagery shows an older low-slope industrial warehouse roof in fair overall condition with moderate serviceability risk. The white roof field has scattered dark staining/discoloration and a somewhat uneven appearance that may indicate prior repairs, weathering, or moisture-related concerns, while the tan field appears more uniform. Multiple penetrations, vents, and curbs are visible, increasing flashing and leak potential on a low

Recommendation:

Have a qualified commercial roofing contractor perform an onsite inspection to verify membrane type, evaluate the visible staining/discoloration, check flashings and penetrations, and perform moisture testing if warranted. If the roof is a restorable low-slope membrane system and no widespread moisture, deck, or substrate failure is found, evaluate a silicone roof restoration option before a more costly overlay or replacement; a qualifying silicone system may reduce tear-off waste, cost, and disruption, create a seamless reflective surface, improve ponding-water tolerance when properly designed and installed, and may qualify for a manufacturer warranty of up to 20 years. If inspection finds widespread moisture, failed insulation, incompatible substrate, or other advanced deterioration, pursue overlay or replacement evaluation instead.

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST

\$2,375,665

\$26.75 / SF

COST SUMMARY

Replacement Subtotal	\$2,065,796
Contingency (15%)	\$309,869
Total Project Cost	\$2,375,665

Roof Overlay Cost Estimate

TOTAL PROJECT COST

\$891,960

\$10.50 / SF

COST SUMMARY

Overlay Subtotal	\$810,873
Contingency (10%)	\$81,087
Total Project Cost	\$891,960

Roof Coating Estimate

TOTAL PROJECT COST

\$270,291 - \$463,356

\$3.50 - \$6.00 / SF

WARRANTY TERM

10 Year Warranty	\$270,291 - \$308,904
15 Year Warranty	\$347,517 - \$386,130
20 Year Warranty	\$424,743 - \$463,356

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.