

5200 E SMITH RD

DENVER CO 80216

PROPERTY TYPE
INDUSTRIAL-WAREHOUSE 401: MFG/PROC...

YEAR BUILT
1964

BUILDING AREA
99,854 SF

ROOF SQUARES
999

PARCEL ID
0119400271000



OVERALL ROOF CONDITION SCORE

59 /100
POOR

RISK LEVEL

HIGH



ROOF INFORMATION

ROOF TYPE	low-slope commercial roof
ROOF SYSTEM	Primary: Primary roof field appears to be a white single-ply or coated low-slope membrane roof; adjacent lower roof areas appear to be a tan low-slope membrane roof with multiple rooftop units and equipment.; Secondary: TPO/PVC
VISIBLE CONCERNS	dark staining/color variation; many penetrations/units; Main white roof field is mostly uniform but shows scattered darker spots and a few localized discolorations that could reflect staining, prior repairs, or minor moisture-related wear.
ROOF AGE EST.	Likely older commercial roof, roughly 15-30+ years apparent by building age and roof layout; exact roof age cannot be confirmed from aerial imagery alone.
ROOF AREA	99,854 SF
ROOF PITCH	Low-slope / near-flat

SELECTED AERIAL IMAGE - DENVER GIS AS OF 03/11/2018 - 03/17/2018

ROOF CONDITION BREAKDOWN

Membrane Condition		62/100
Ponding		64/100
Flashing & Seals		54/100
Penetrations		50/100
Overall Maintenance		56/100

AERIAL ROOF OBSERVATIONS

1. Main roof field is bright white and generally uniform, suggesting a reflective low-slope membrane or coated surface.
2. Several small rooftop penetrations and mechanical items are distributed across the main field.
3. Adjacent lower roof areas are more heavily populated with rooftop equipment and ductwork, increasing service complexity.
4. Localized dark spots/discoloration are visible on the white field.
5. No clear tree overhang or major debris accumulation is visible in the roof areas shown.

BUILDING CHARACTERISTICS

LAND AREA	9.53 acres
STORIES	-
CONSTRUCTION TYPE	401: MFG/PROCESSING
TAX DISTRICT	DENV
LAND VALUE	\$4,979,400

REPORT SUMMARY

Aerial imagery dated 03/11/2018 - 03/17/2018 shows a large low-slope industrial roof with a predominantly white reflective membrane on the main field and a more equipment-dense tan roof area adjacent to it. The main roof appears generally serviceable, but scattered discoloration and the presence of multiple penetrations and rooftop units increase leak and flashing risk. No obvious ponding is visible, though drainage performance cannot be verified from aerial-only imagery

Recommendation:

Recommend a qualified commercial roofing contractor perform an onsite inspection to confirm roof system type, condition, flashing integrity, drainage, and any moisture-related issues; moisture testing should be performed where warranted. For the apparently restorable low-slope white roof area, evaluate silicone roof restoration before a more costly overlay or replacement, provided the substrate and warranty criteria are confirmed and needed repairs/preparation are completed. A properly designed and installed silicone system can create a seamless monolithic white reflective cool-roof surface, may reduce tear-off waste, cost, and disruption, can improve UV and hail resistance, withstand ponding water when properly designed and installed, and may qualify for a manufacturer warranty of up to 20 years. If onsite findings reveal widespread moisture, failed insulation, deck deterioration, or an incompatible substrate, then overlay or full roof

ROOF REPAIR OPTIONS

Roof Replacement Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$2,928,219	Replacement Subtotal \$2,546,277
\$25.50 / SF	Contingency (15%) \$381,942
	Total Project Cost \$2,928,219

Roof Overlay Cost Estimate

TOTAL PROJECT COST	COST SUMMARY
\$1,098,394	Overlay Subtotal \$998,540
\$10.00 / SF	Contingency (10%) \$99,854
	Total Project Cost \$1,098,394

Roof Coating Estimate

TOTAL PROJECT COST	WARRANTY TERM	BUDGETARY COST RANGE
\$349,489 - \$599,124	10 Year Warranty	\$349,489 - \$399,416
\$3.50 - \$6.00 / SF	15 Year Warranty	\$449,343 - \$499,270
	20 Year Warranty	\$549,197 - \$599,124

Cost estimates are derived from publicly available information and proprietary commercial roofing analysis models and are intended for preliminary budgeting and planning purposes only. Roof-area measurements do not include the vertical surface area of parapet walls. They should not be considered a contractor quote, engineering assessment, or guarantee of actual project costs. Estimates do not include additional repairs or unforeseen conditions that may be identified during an on-site inspection.